

NFPA®

1963

**Standard for
Fire Hose Connections**

2019



IMPORTANT NOTICES AND DISCLAIMERS CONCERNING NFPA® STANDARDS

NFPA® codes, standards, recommended practices, and guides (“NFPA Standards”), of which the document contained herein is one, are developed through a consensus standards development process approved by the American National Standards Institute. This process brings together volunteers representing varied viewpoints and interests to achieve consensus on fire and other safety issues. While the NFPA administers the process and establishes rules to promote fairness in the development of consensus, it does not independently test, evaluate, or verify the accuracy of any information or the soundness of any judgments contained in NFPA Standards.

The NFPA disclaims liability for any personal injury, property, or other damages of any nature whatsoever, whether special, indirect, consequential or compensatory, directly or indirectly resulting from the publication, use of, or reliance on NFPA Standards. The NFPA also makes no guaranty or warranty as to the accuracy or completeness of any information published herein.

In issuing and making NFPA Standards available, the NFPA is not undertaking to render professional or other services for or on behalf of any person or entity. Nor is the NFPA undertaking to perform any duty owed by any person or entity to someone else. Anyone using this document should rely on his or her own independent judgment or, as appropriate, seek the advice of a competent professional in determining the exercise of reasonable care in any given circumstances.

The NFPA has no power, nor does it undertake, to police or enforce compliance with the contents of NFPA Standards. Nor does the NFPA list, certify, test, or inspect products, designs, or installations for compliance with this document. Any certification or other statement of compliance with the requirements of this document shall not be attributable to the NFPA and is solely the responsibility of the certifier or maker of the statement.

REVISION SYMBOLS IDENTIFYING CHANGES FROM THE PREVIOUS EDITION

Text revisions are shaded. A **Δ** before a section number indicates that words within that section were deleted and a **Δ** to the left of a table or figure number indicates a revision to an existing table or figure. When a chapter was heavily revised, the entire chapter is marked throughout with the **Δ** symbol. Where one or more sections were deleted, a **•** is placed between the remaining sections. Chapters, annexes, sections, figures, and tables that are new are indicated with an **N**.

Note that these indicators are a guide. Rearrangement of sections may not be captured in the markup, but users can view complete revision details in the First and Second Draft Reports located in the archived revision information section of each code at www.nfpa.org/docinfo. Any subsequent changes from the NFPA Technical Meeting, Tentative Interim Amendments, and Errata are also located there.

REMINDER: UPDATING OF NFPA STANDARDS

Users of NFPA codes, standards, recommended practices, and guides (“NFPA Standards”) should be aware that these documents may be superseded at any time by the issuance of a new edition, may be amended with the issuance of Tentative Interim Amendments (TIAs), or be corrected by Errata. It is intended that through regular revisions and amendments, participants in the NFPA standards development process consider the then-current and available information on incidents, materials, technologies, innovations, and methods as these develop over time and that NFPA Standards reflect this consideration. Therefore, any previous edition of this document no longer represents the current NFPA Standard on the subject matter addressed. NFPA encourages the use of the most current edition of any NFPA Standard [as it may be amended by TIA(s) or Errata] to take advantage of current experience and understanding. An official NFPA Standard at any point in time consists of the current edition of the document, including any issued TIAs and Errata then in effect.

To determine whether an NFPA Standard has been amended through the issuance of TIAs or corrected by Errata, visit the “Codes & Standards” section at www.nfpa.org.

ADDITIONAL IMPORTANT NOTICES AND DISCLAIMERS CONCERNING NFPA® STANDARDS

Updating of NFPA Standards

Users of NFPA codes, standards, recommended practices, and guides (“NFPA Standards”) should be aware that these documents may be superseded at any time by the issuance of a new edition, may be amended with the issuance of Tentative Interim Amendments (TIAs), or be corrected by Errata. It is intended that through regular revisions and amendments, participants in the NFPA standards development process consider the then-current and available information on incidents, materials, technologies, innovations, and methods as these develop over time and that NFPA Standards reflect this consideration. Therefore, any previous edition of this document no longer represents the current NFPA Standard on the subject matter addressed. NFPA encourages the use of the most current edition of any NFPA Standard [as it may be amended by TIA(s) or Errata] to take advantage of current experience and understanding. An official NFPA Standard at any point in time consists of the current edition of the document, including any issued TIAs and Errata then in effect.

To determine whether an NFPA Standard has been amended through the issuance of TIAs or corrected by Errata, visit the “Codes & Standards” section at www.nfpa.org.

Interpretations of NFPA Standards

A statement, written or oral, that is not processed in accordance with Section 6 of the Regulations Governing the Development of NFPA Standards shall not be considered the official position of NFPA or any of its Committees and shall not be considered to be, nor be relied upon as, a Formal Interpretation.

Patents

The NFPA does not take any position with respect to the validity of any patent rights referenced in, related to, or asserted in connection with an NFPA Standard. The users of NFPA Standards bear the sole responsibility for determining the validity of any such patent rights, as well as the risk of infringement of such rights, and the NFPA disclaims liability for the infringement of any patent resulting from the use of or reliance on NFPA Standards.

NFPA adheres to the policy of the American National Standards Institute (ANSI) regarding the inclusion of patents in American National Standards (“the ANSI Patent Policy”), and hereby gives the following notice pursuant to that policy:

NOTICE: The user’s attention is called to the possibility that compliance with an NFPA Standard may require use of an invention covered by patent rights. NFPA takes no position as to the validity of any such patent rights or as to whether such patent rights constitute or include essential patent claims under the ANSI Patent Policy. If, in connection with the ANSI Patent Policy, a patent holder has filed a statement of willingness to grant licenses under these rights on reasonable and nondiscriminatory terms and conditions to applicants desiring to obtain such a license, copies of such filed statements can be obtained, on request, from NFPA. For further information, contact the NFPA at the address listed below.

Law and Regulations

Users of NFPA Standards should consult applicable federal, state, and local laws and regulations. NFPA does not, by the publication of its codes, standards, recommended practices, and guides, intend to urge action that is not in compliance with applicable laws, and these documents may not be construed as doing so.

Copyrights

NFPA Standards are copyrighted. They are made available for a wide variety of both public and private uses. These include both use, by reference, in laws and regulations, and use in private self-regulation, standardization, and the promotion of safe practices and methods. By making these documents available for use and adoption by public authorities and private users, the NFPA does not waive any rights in copyright to these documents.

Use of NFPA Standards for regulatory purposes should be accomplished through adoption by reference. The term “adoption by reference” means the citing of title, edition, and publishing information only. Any deletions, additions, and changes desired by the adopting authority should be noted separately in the adopting instrument. In order to assist NFPA in following the uses made of its documents, adopting authorities are requested to notify the NFPA (Attention: Secretary, Standards Council) in writing of such use. For technical assistance and questions concerning adoption of NFPA Standards, contact NFPA at the address below.

For Further Information

All questions or other communications relating to NFPA Standards and all requests for information on NFPA procedures governing its codes and standards development process, including information on the procedures for requesting Formal Interpretations, for proposing Tentative Interim Amendments, and for proposing revisions to NFPA standards during regular revision cycles, should be sent to NFPA headquarters, addressed to the attention of the Secretary, Standards Council, NFPA, 1 Batterymarch Park, P.O. Box 9101, Quincy, MA 02269-9101; email: stds_admin@nfpa.org.

For more information about NFPA, visit the NFPA website at www.nfpa.org. All NFPA codes and standards can be viewed at no cost at www.nfpa.org/docinfo.

Copyright © 2018 National Fire Protection Association®. All Rights Reserved.

NFPA® 1963

Standard for

Fire Hose Connections

2019 Edition

This edition of NFPA 1963, *Standard for Fire Hose Connections*, was prepared by the Technical Committee on Fire Hose. It was issued by the Standards Council on November 5, 2018, with an effective date of November 25, 2018, and supersedes all previous editions.

This edition of NFPA 1963 was approved as an American National Standard on November 25, 2018.

Origin and Development of NFPA 1963

The development of a standard for screw threads and gaskets for fire hose connections began over a century ago. Specifications for hose couplings were drawn up by the NFPA as early as 1898. An NFPA committee appointed in 1905 established a national standard thread for 2 1/2 in. and larger hose connections. Work on smaller hose threads was started in 1916, and the standard was adopted in 1922. The standard for suction hose coupling threads was adopted in 1955. The present standard covers the 11 standard sizes of threaded connections from 3/4 in. to 8 in. (19 mm to 200 mm).

See Annex B for a detailed history of fire hose coupling thread standardization in the United States.

In recent history, editions of this standard were published in 1979, 1985, 1993, 1998, and 2003. The 1979 edition included metric conversion figures where applicable. Also, the number designation of the document was changed from NFPA 194 to NFPA 1963. Changes in 1985 were editorial.

The 1993 edition was a major expansion of the standard. A new chapter was added to cover general requirements for couplings and adapters. Another was added to cover nonthreaded connections in the 4 in. and 5 in. (100 mm and 125 mm) sizes. New material was added to the chapter on gaskets to cover gaskets used with nonthreaded connections. Sections dealing with the threads on fire department pump discharges and intakes, portable pumps, and sprinkler and standpipe systems were deleted because requirements addressing those threads are covered in other NFPA standards. The title of the document was changed from *Standard for Screw Threads and Gaskets for Fire Hose Connections* to *Standard for Fire Hose Connections* to reflect the broader scope of the document.

In the 1998 edition, the requirement for locks on caps used with nonthreaded couplings was removed, and some editorial revisions were made to the document.

The 2003 edition added dimensioning for an 8 in. (200 mm) NH thread. Format revisions were made to meet the requirements of the *Manual of Style for NFPA Technical Committee Documents*.

The 2009 edition permitted the use of pressure-only gaskets in nonthreaded caps for known pressure-only applications.

For the 2014 edition, the committee brought the equations into conformity with the *Manual of Style for NFPA Technical Committee Documents*. The committee also permitted all nonthreaded adapters to have gaskets but not necessarily pressure gaskets.

For the 2019 edition, the committee added many new requirements that were in NFPA 1965 because the committee is withdrawing NFPA 1965. A thorough comparison of NFPA 1963 and NFPA 1965 was completed by the committee and, where applicable, those requirements that were in NFPA 1965 that would pertain to NFPA 1963 were added to NFPA 1963. Given the amount of material that was moved from NFPA 1965 to NFPA 1963 for the 2019 edition, it would be best to refer to the document information page at www.nfpa.org for all of the specific added requirements.

Technical Committee on Fire Hose

Andrew D. Ellison, *Chair*
Unified Investigations and Science, MA [SE]

Jason Goodale, *Secretary*
Loveland Fire Rescue, CO [U]

Michael S. Aubuchon, Sr., North American Fire Hose Corporation, CA [M]

Bill C. Betz, Fairfax County Fire & Rescue Department, VA [U]

Christopher B. Budzinski, City of Asheville Fire Department, NC [E]

Jonathan R. Cares, Town of Londonderry Fire Rescue, NH [U]

Michael Cedrone, FM Global, RI [I]
Rep. FM Global

Jesse Edwards, All-American Hose, PA [M]

Brian Fink, Fire Department City of New York, NY [E]
Rep. Fire Department City of New York

James E. Glatts, FireOne, PA [IM]

Sean Gray, Cobb County Fire And Emergency Services, GA [SE]

Jeff Hebenstreit, UL LLC, IL [RT]

Stephen Jackson, Waterway Hudson Valley, NY [IM]

Jayme L. Kahle, Rincon Valley Fire District, AZ [E]

Brian P. Kazmierzak, Penn Township Fire Department, IN [E]

Duane Leonhardt, Mercedes Textiles Ltd., Canada [M]
Rep. Fire Equipment Manufacturers' Association

Mark Allen Lighthill, KFH Industries, AL [M]

Michael Mayer, Task Force Tips, IN [M]

David Quick, Manchester Fire Department, NH [U]

Marc T. Radecky, FireCatt, LLC, MI [IM]

Jason D. Riggenschach, IDEX Corp/Akron Brass Company, OH [M]

John D. Schreiber, Colorado Springs Fire Department, CO [U]

John W. Stacey, Glenwood, IA [E]
Rep. International Association of Fire Chiefs

Tim Vanderlip, Los Angeles County Fire Department, CA [U]

David Walsh, Boston Fire Department, MA [E]

Samuel Wu, U.S. Department of Agriculture, CA [RT]

Alternates

Jeffrey L. Benson, IDEX Corp/Akron Brass Company, OH [M]
(Alt. to Jason D. Riggenschach)

Gregg Burzine, Fire Department City of New York, NY [E]
(Alt. to Brian Fink)

Jim Ford, Waterway North Jersey, NJ [IM]
(Alt. to Stephen Jackson)

Gregory Kozey, Koche Company, Inc., CT [M]
(Voting Alternate)

Douglas Menard, Boston Fire Department, MA [U]
(Alt. to David Walsh)

Ronald Nathan Miller, Asheville Fire Department, NC [E]
(Alt. to Christopher B. Budzinski)

Nicholas A. Nava, Exponent, MD [SE]
(Voting Alternate)

Nick Keith Proulx, Gilford, NH [U]
(Alt. to David Quick)

Ron Stanley, All-American Hose, PA [M]
(Alt. to Jesse Edwards)

Jacqueline Wilmot, NFPA Staff Liaison

This list represents the membership at the time the Committee was balloted on the final text of this edition. Since that time, changes in the membership may have occurred. A key to classifications is found at the back of the document.

NOTE: Membership on a committee shall not in and of itself constitute an endorsement of the Association or any document developed by the committee on which the member serves.

Committee Scope: This Committee shall have primary responsibility for documents on the size and design of fire hose connections, and the performance, maintenance, and selection of all types of fire hose, couplings, nozzles, and accessory equipment.

Contents

Chapter 1 Administration	1963- 4	5.2 Thread Series Designation.	1963- 8
1.1 Scope.	1963- 4	5.3 Dimensions of American National Fire Hose Connection Screw Threads (NH).	1963- 9
1.2 Purpose.	1963- 4	5.4 Thread Dimensions.	1963- 9
1.3 Application.	1963- 4	5.5 Tolerance.	1963- 9
Chapter 2 Referenced Publications	1963- 4	5.6 Gauges and Gauging NH Threads.	1963- 12
2.1 General.	1963- 4	Chapter 6 Nonthreaded Connections	1963- 15
2.2 NFPA Publications.	1963- 4	6.1 General.	1963- 15
2.3 Other Publications.	1963- 4	6.2 Gauges.	1963- 15
2.4 References for Extracts in Mandatory Sections.	1963- 5	6.3 Locks.	1963- 15
Chapter 3 Definitions	1963- 5	6.4 Indicators.	1963- 16
3.1 General.	1963- 5	6.5 Force to Connect and Disconnect.	1963- 16
3.2 NFPA Official Definitions.	1963- 5	6.6 Caps.	1963- 17
3.3 General Definitions.	1963- 5	6.7 Adapters.	1963- 17
Chapter 4 General Coupling and Adapter Requirements	1963- 5	6.8 Hydrant and Fire Department Connections. .	1963- 17
4.1 Workmanship.	1963- 5	Chapter 7 Gaskets	1963- 19
4.2 Materials.	1963- 5	7.1 Threaded Coupling Gasket.	1963- 19
4.3 Minimum Waterway.	1963- 6	7.2 Nonthreaded Connection Gaskets.	1963- 19
4.4 Gasket Groove.	1963- 6	7.3 Tail Gasket.	1963- 19
4.5 Testing.	1963- 6	Chapter 8 Use of NH Threads and Nonthreaded Connections	1963- 20
4.6 Internal Strength.	1963- 6	8.1 Hose Coupling Threads.	1963- 20
4.7 Tensile Strength.	1963- 6	8.2 Connections for Fire Service Nozzles for Handlines.	1963- 20
4.8 Connect/Disconnect Capability.	1963- 6	8.3 Connections for Large-Stream Devices.	1963- 21
4.9 Rough Usage.	1963- 6	Annex A Explanatory Material	1963- 22
4.10 Coupling Retention.	1963- 7	Annex B History of Fire Hose Coupling Thread Standardization in the United States	1963- 26
4.11 Vacuum Tightness.	1963- 7	Annex C Informational References	1963- 27
4.12 Corrosion Resistance.	1963- 7	Index	1963- 28
4.13 Nonmetallic Materials.	1963- 7		
4.14 High-Temperature Performance.	1963- 7		
4.15 Low-Temperature Performance.	1963- 7		
4.16 Gasket Performance.	1963- 7		
4.17 Marking.	1963- 8		
Chapter 5 Screw Threads for Couplings and Adapters	1963- 8		
5.1 Basic Form of Thread.	1963- 8		

NFPA 1963

Standard for

Fire Hose Connections

2019 Edition

IMPORTANT NOTE: This NFPA document is made available for use subject to important notices and legal disclaimers. These notices and disclaimers appear in all publications containing this document and may be found under the heading “Important Notices and Disclaimers Concerning NFPA Standards.” They can also be viewed at www.nfpa.org/disclaimers or obtained on request from NFPA.

UPDATES, ALERTS, AND FUTURE EDITIONS: New editions of NFPA codes, standards, recommended practices, and guides (i.e., NFPA Standards) are released on scheduled revision cycles. This edition may be superseded by a later one, or it may be amended outside of its scheduled revision cycle through the issuance of Tentative Interim Amendments (TIAs). An official NFPA Standard at any point in time consists of the current edition of the document, together with all TIAs and Errata in effect. To verify that this document is the current edition or to determine if it has been amended by TIAs or Errata, please consult the National Fire Codes® Subscription Service or the “List of NFPA Codes & Standards” at www.nfpa.org/docinfo. In addition to TIAs and Errata, the document information pages also include the option to sign up for alerts for individual documents and to be involved in the development of the next edition.

NOTICE: An asterisk (*) following the number or letter designating a paragraph indicates that explanatory material on the paragraph can be found in Annex A.

A reference in brackets [] following a section or paragraph indicates material that has been extracted from another NFPA document. As an aid to the user, the complete title and edition of the source documents for extracts in mandatory sections of the document are given in Chapter 2 and those for extracts in informational sections are given in Annex C. Extracted text may be edited for consistency and style and may include the revision of internal paragraph references and other references as appropriate. Requests for interpretations or revisions of extracted text shall be sent to the technical committee responsible for the source document.

Information on referenced publications can be found in Chapter 2 and Annex C.

Chapter 1 Administration

1.1* Scope.

1.1.1 This standard gives the performance and requirements for new fire hose couplings and adapters with nominal sizes from ¾ in. (19 mm) through 8 in. (200 mm) and the specifications for the screw thread connections on those couplings and adapters.

1.1.2 This standard also gives the performance and requirements for the mating surfaces of nonthreaded fire hose couplings and adapters with nominal sizes of 4 in. (100 mm) and 5 in. (125 mm).

1.2 Purpose. The purpose of this standard is to provide a uniform standard for safe couplings and adapters for the users of fire hose connections.

1.3 Application.

1.3.1 The requirements of this standard shall apply to the following coupling and adapters in the sizes defined in Section 1.1.

- (1) Fire hose couplings
- (2) Booster hose couplings
- (3) Suction hose couplings
- (4) Adapters
- (5) Reducers
- (6) Caps
- (7) Plugs
- (8) Connections on fire hose appliances where they attach to fire hose

Δ **1.3.2** The requirements of this standard shall also apply to screw thread connections and nonthreaded mating surfaces on the following devices in the sizes defined in Section 1.1:

- (1) Pump intake connections on fire apparatus
- (2) Pump discharge connections on fire apparatus
- (3) Sprinkler connections
- (4) Standpipe connections
- (5) Hose connections on fire hydrants
- (6) Connections on all other hose fittings and appliances that attach to fire pumps, fire hose, or hydrants

Chapter 2 Referenced Publications

2.1 General. The documents or portions thereof listed in this chapter are referenced within this standard and shall be considered part of the requirements of this document.

2.2 NFPA Publications. National Fire Protection Association, 1 Batterymarch Park, Quincy, MA 02169-7471.

NFPA 1971, *Standard on Protective Ensembles for Structural Fire Fighting and Proximity Fire Fighting*, 2018 edition.

2.3 Other Publications.

Δ **2.3.1 ASME Publications.** ASME International, Two Park Avenue, New York, NY 10016-5990.

ASME B1.2, *Gages and Gaging for Unified Inch Screw Threads*, 83rd edition, 1991, reaffirmed 2007.

Δ **2.3.2 ASTM Publications.** ASTM International, 100 Barr Harbor Drive, P.O. Box C700, West Conshohocken, PA 19428-2959.

ASTM B30, *Standard Specification for Copper Alloys in Ingot Form*, 2016.

ASTM B117, *Standard Practice for Operating Salt Spray (Fog) Apparatus*, 2016.

ASTM B584, *Standard Specification for Copper Alloy Sand Castings for General Applications*, 2014.

ASTM D395, *Standard Test Methods for Rubber Property — Compression Set*, 2016.

ASTM D573, *Standard Test Method for Rubber Deterioration in an Air Oven*, 2004, reapproved 2015.

ASTM D3183, *Standard Practice for Rubber — Preparation of Pieces for Test Purposes from Products*, 2010, reapproved 2015.

2.3.3 Other Publications.

Merriam-Webster's Collegiate Dictionary, 11th edition, Merriam-Webster, Inc., Springfield, MA, 2003.

2.4 References for Extracts in Mandatory Sections.

NFPA 24, *Standard for the Installation of Private Fire Service Mains and Their Appurtenances*, 2019 edition.

NFPA 1961, *Standard for Fire Hose*, 2013 edition.

NFPA 1964, *Standard for Spray Nozzles*, 2018 edition.

Chapter 3 Definitions

3.1 General. The definitions contained in this chapter shall apply to the terms used in this standard. Where terms are not defined in this chapter or within another chapter, they shall be defined using their ordinarily accepted meanings within the context in which they are used. *Merriam-Webster's Collegiate Dictionary*, 11th edition, shall be the source for the ordinarily accepted meaning.

3.2 NFPA Official Definitions.

3.2.1* Approved. Acceptable to the authority having jurisdiction.

3.2.2* Authority Having Jurisdiction (AHJ). An organization, office, or individual responsible for enforcing the requirements of a code or standard, or for approving equipment, materials, an installation, or a procedure.

3.2.3 Shall. Indicates a mandatory requirement.

3.2.4 Should. Indicates a recommendation or that which is advised but not required.

3.3 General Definitions.

3.3.1 Adapter. Any device that allows fire hose couplings to be safely interconnected with couplings of different sizes, threads, or mating surfaces, or that allows fire hose couplings to be safely connected to other appliances.

3.3.1.1 Nonthreaded Coupling or Adapter. A coupling or adapter in which the mating is achieved with locks or cams but without the use of screw threads.

3.3.1.2 Screw Thread Coupling or Adapter. A coupling or adapter in which the mating is achieved with the use of threads.

3.3.2 Blunt Start. The removal of the incomplete thread at the end of the thread. This is a feature of threaded parts that are repeatedly assembled by hand. Also known as the "Higbee cut."

3.3.3 Bowl Gasket. See 3.3.8.1.

3.3.4 Coupling Assembly. A complete coupling including its gaskets and the expansion rings or collar pieces used in attaching the coupling to the hose.

3.3.5 Couplings. One set or pair of connection devices attached to a fire hose that allow the hose to be interconnected to additional lengths of hose or adapters and other fire-fighting appliances.

3.3.6 Face Gasket. See 3.3.8.2.

3.3.7 Fire Department Connection. A connection through which the fire department can pump supplemental water into the sprinkler system, standpipe, or other water-based fire protection systems, thereby supplementing existing water supplies. [24, 2019]

3.3.8 Gasket.

3.3.8.1 Bowl Gasket. See *Tail Gasket*.

3.3.8.2 Face Gasket. The water pressure seal at the mating surfaces of nonthreaded couplings or adapters.

3.3.8.3 Tail Gasket. A gasket in the bowl of a coupling used to provide a watertight seal between the coupling and the hose in an expansion ring-type coupling.

3.3.8.4 Thread Gasket. A gasket used in a female threaded connection to provide a watertight seal between the male and female threaded connections.

3.3.9 Large-Stream Device. Any device that discharges water at a flow rate greater than 400 gpm (1600 L/min).

3.3.10 NH. An American National Fire Hose Connection Screw Thread. (See *Section 5.2*.)

3.3.11 Nonthreaded Coupling or Adapter. See 3.3.1.1.

3.3.12 Nozzle.

3.3.12.1 Spray Nozzle. A nozzle intended for connection to a hose line or monitor to discharge water in either a spray pattern or a straight stream pattern as selected by the operator. [1964, 2018]

3.3.12.2 Straight Tip Nozzle. A smooth-bore nozzle for producing a solid stream.

3.3.13 Primary Inlet. The inlet where an appliance connects to a hose.

3.3.14 Screw Thread Coupling or Adapter. See 3.3.1.2.

3.3.15 Spray Nozzle. See 3.3.12.1.

3.3.16 Straight Tip Nozzle. See 3.3.12.2.

3.3.17 Suction Hose. A hose that is designed to prevent collapse under vacuum conditions so that it can be used for drafting water from below the pump (lakes, rivers, wells, etc.). [1961, 2013]

3.3.18 Tail Gasket. See 3.3.8.3.

3.3.19 Thread Gasket. See 3.3.8.4.

Chapter 4 General Coupling and Adapter Requirements

4.1* Workmanship. The coupling assembly or adapter shall be made and finished in a workmanship-like manner throughout.

4.1.1 All edges shall be chamfered and free from burrs.

4.1.2 Hose bowl or tailpiece lips shall be rounded to prevent damage to the hose.

4.2 Materials. Materials used shall be free of defects that would adversely affect the performance or maintenance of individual components or of the overall assembly.

4.3 Minimum Waterway. The design of the shank-type and nonthreaded expansion ring coupling shall be such that the coupling shall not restrict the waterway by more than $\frac{1}{4}$ in. (6.4 mm) on couplings of nominal size $2\frac{1}{2}$ in. (65 mm) or less and not more than $\frac{1}{2}$ in. (12.7 mm) on couplings of nominal size greater than $2\frac{1}{2}$ in. (65 mm). Gaskets shall not protrude into the waterway.

4.3.1 The waterway of a size-increasing-style coupling, other than a shank-type coupling, shall be no smaller than the nominal size of the hose to which it is attached.

4.3.2 The waterway of a size-reducing-style coupling, other than a shank-type coupling, shall be no smaller than the nominal size of the attachment face.

4.4 Gasket Groove. All sizes of internal NH threaded couplings, connections, or adapters shall have a standard gasket groove diameter as shown in Table 5.4.2, column K. (See also Figure 5.1.5.1, dimension K.)

4.5 Testing. Tests required by this standard shall be conducted by the manufacturer or by an approved testing facility designated by the manufacturer.

4.5.1 All tests shall be conducted on standard commercially available product.

4.5.2 Any test that requires the use of hose shall use hose with the highest service test pressure commercially available to which the coupling can be attached.

4.6 Internal Strength.

4.6.1 The coupling or adapter shall be capable of withstanding a hydrostatic pressure equal to the service test pressure without leakage, two times service test pressure with no leakage more severe than 12 drops per minute ($\frac{1}{2}$ ml per minute), and three times the service test pressure plus 100 psi (690 kPa) without separation. It shall be tested in accordance with 4.6.2 to prove compliance.

4.6.2 Internal Strength Test.

4.6.2.1 The coupling or adapter shall be plugged and adapted on one end to accept a pump connection from a hydrostatic test table.

4.6.2.2 The other end shall be plugged or adapted to accept a petcock to remove air.

4.6.2.3 The coupling or adapter shall be filled with water until all air has been exhausted and the petcock closed.

4.6.2.4 Pressure shall be applied until the test pressure is reached.

4.6.2.5 The test pressure shall be held for at least 15 seconds but not more than 60 seconds.

4.7 Tensile Strength.

4.7.1 Couplings shall have a tensile strength of at least 1200 lb/in. (210 N/mm) of diameter. They shall be tested in accordance with 4.7.2 to prove compliance.

4.7.2 Tensile Strength Test.

4.7.2.1 A pair of couplings shall be attached to a section of hose.

4.7.2.2 The couplings shall be connected together and the hose installed in a tension testing machine such that the tension will be on the couplings.

4.7.2.3 A tensile load shall be applied at a rate of not more than 2 in. (51 mm) per minute up to 1200 lb/in. (210 N/mm) of nominal hose diameter.

4.7.3 After the tensile strength test, the couplings shall be subjected to a test pressure equal to the service test pressure of the hose to which they are attached. Any leakage or deformation shall constitute failure of this test.

4.8 Connect/Disconnect Capability.

4.8.1 Couplings shall be capable of being connected and disconnected at least 3000 times without leakage or failure. They shall be tested in accordance with 4.8.2 to prove compliance.

4.8.2 Connect/Disconnect Capability Test.

4.8.2.1 Tests shall be conducted on standard commercial product without lubrication.

4.8.2.2 Hose couplings shall be completely connected and disconnected to each other at least 3000 times.

4.8.2.3 At the completion of this portion of the test, the couplings shall be attached to hose such that tested couplings can be connected together.

4.8.2.4 The tested couplings when connected together shall withstand the service test pressure of the hose without leakage or failure.

4.9 Rough Usage.

4.9.1 Couplings shall be capable of being dropped up to 6 ft (1.8 m) without deformation or damage that impairs operation. They shall be tested in accordance with 4.9.2 to prove compliance.

4.9.2 Rough Usage Test.

4.9.2.1 Couplings shall be installed on approximately 10 ft (3 m) lengths of fire hose.

4.9.2.2 The couplings shall be coupled together, forming a loop in the hose.

4.9.2.3 The coupling assembly shall then be dropped onto a concrete surface from a height of 6 ft (1.8 m) so as to land as squarely as possible on the swivel ring.

4.9.2.4 The procedure in 4.9.2.3 shall be repeated three times.

4.9.2.5 The couplings shall operate freely and shall show no signs of deformation when inspected inside and outside.

4.9.2.6 Samples showing distortion or binding of the swivel mechanism shall be judged acceptable if the mechanism can be corrected to turn freely and evenly when straightened by the use of a hammer.

4.9.2.7 Samples developing cracks or broken sections either before or after attempts to straighten damaged portions shall be deemed as having failed the test. The coupling/hose assembly shall withstand the service test pressure of the hose without leakage or failure.

4.10 Coupling Retention.

4.10.1 Couplings shall remain on the hose without movement up to the rated burst pressure of the hose. They shall be tested in accordance with 4.10.2 to prove compliance.

4.10.2 Coupling Retention Test.

4.10.2.1 The couplings shall be attached to a 3 ft (1 m) length of hose.

4.10.2.2 The hose and coupling as an assembly shall be pressurized to the service pressure of the hose for 1 minute, and then the pressure shall be released.

4.10.2.3 The position of the coupling with relation to the hose shall be marked.

4.10.2.4 The pressure in the hose/coupling assembly shall then be raised at a rate of 300 psi/min to 1000 psi/min (2068 kPa/min to 6895 kPa/min) until the rated burst pressure of the hose is reached.

4.10.2.5 The pressure shall be held for a minimum of 15 seconds but not longer than 60 seconds.

4.10.2.6 The hose shall show no signs of movement from the coupling.

4.11 Vacuum Tightness.

4.11.1 When couplings are used on suction hose, they shall be capable of holding a vacuum of 22 in. Hg (74.2 kPa) for 5 minutes. They shall be tested in accordance with 4.11.2 to prove compliance.

4.11.2 Vacuum Tightness Test.

4.11.2.1 The coupling shall be attached to a suitable section of suction hose.

4.11.2.2 A blank cap shall be attached to the coupling on one end, and a vacuum pump shall be attached to the other end.

4.11.2.3 A vacuum of 22 in. Hg (74.2 kPa) shall be developed within the assembly, and the assembly shall hold the vacuum for 5 minutes without any loss of vacuum.

4.12 Corrosion Resistance.

4.12.1 Couplings having parts other than high-strength yellow brass No. 8A as defined in ASTM B30, *Standard Specification for Copper Alloys in Ingot Form*, or ASTM B584, *Standard Specification for Copper Alloy Sand Castings for General Applications*, shall be capable of being coupled and uncoupled using accepted standard practices and shall not show any evidence of galvanic corrosion between dissimilar metals after testing in accordance with 4.12.2.

4.12.2 Coupling assemblies, including expansion rings and gaskets, shall be supported vertically in a fog chamber and exposed to salt spray (fog) as specified by ASTM B117, *Standard Practice for Operating Salt Spray (Fog) Apparatus*, for a period of 120 hours.

4.13 Nonmetallic Materials. Any nonmetallic material used in couplings except for the gaskets shall be certified by the manufacturer of the nonmetallic material as fit for the service intended.

4.14 High-Temperature Performance.

4.14.1 Temperatures up to 275°F (135°C) shall not affect the ease with which a coupling assembly is coupled or uncoupled. Couplings shall be tested in accordance with 4.14.2 to prove compliance.

4.14.2 High-Temperature Performance Test.

4.14.2.1 Dry couplings with gaskets installed shall be conditioned in an oven at 275°F (135°C) for 4 hours.

4.14.2.2 Immediately upon their removal from the oven, the torque to connect and disconnect the couplings shall be measured and shall be within the original torque range.

4.15 Low-Temperature Performance.

4.15.1 Temperatures down to $-25^{\circ}\text{F} \pm 2^{\circ}\text{F}$ ($-32^{\circ}\text{C} \pm 1^{\circ}\text{C}$) shall not affect the performance of the coupling assembly. Couplings shall be tested in accordance with 4.15.2 to prove compliance.

4.15.2 Low-Temperature Performance Test.

4.15.2.1 With the gasket(s) installed, a coupling assembly shall be subjected to an environment of $0^{\circ}\text{F} \pm 1^{\circ}\text{F}$ ($-18^{\circ}\text{C} \pm 1^{\circ}\text{C}$) for a period of 24 hours and subsequently to an environment of $-25^{\circ}\text{F} \pm 2^{\circ}\text{F}$ ($-32^{\circ}\text{C} \pm 1^{\circ}\text{C}$) for a period of 2 hours.

4.15.2.2 Following this exposure, the coupling shall be dropped from a height of 10 ft (3 m) onto its longitudinal axis.

4.15.2.3 The torque to connect and disconnect the couplings shall then be measured and shall be no greater than the torque required before the test.

4.16 Gasket Performance. The gasket material used with any coupling or adapter shall meet the test requirements of 4.16.1 through 4.16.3.

4.16.1 Low-Temperature Test.

4.16.1.1 Gaskets shall be subjected to an environment of $0^{\circ}\text{F} \pm 1^{\circ}\text{F}$ ($-18^{\circ}\text{C} \pm 1^{\circ}\text{C}$) for a period of 24 hours and subsequently to an environment of $-25^{\circ}\text{F} \pm 2^{\circ}\text{F}$ ($-32^{\circ}\text{C} \pm 1^{\circ}\text{C}$) for a period of 2 hours.

4.16.1.2 Immediately upon removal from the test chamber, the gasket shall not crack when squeezed from any two opposite points into a figure 8 configuration.

4.16.2 Accelerated Aging Test.

4.16.2.1 Samples of the gasket material shall be prepared in accordance with the procedures described in ASTM D3183, *Standard Practice for Rubber — Preparation of Pieces for Test Purposes from Products*.

4.16.2.2 The samples of the gaskets shall then be subjected to oven aging at $212^{\circ}\text{F} \pm 3^{\circ}\text{F}$ ($100^{\circ}\text{C} \pm 2^{\circ}\text{C}$) for 70 hours in accordance with ASTM D573, *Standard Test Method for Rubber — Deterioration in an Air Oven*.

4.16.2.3 The samples shall then be tested for tensile strength and ultimate elongation, and the tensile strength shall be not less than 80 percent, and the ultimate elongation shall be not less than 50 percent of the corresponding properties of samples that have not been so treated.

4.16.3 Compression Set Test.

4.16.3.1 A sample of gasket material shall be compressed as defined in Method B of ASTM D395, *Standard Test Methods for Rubber Property — Compression Set*, and subjected to heat treatment at $158^{\circ}\text{F} \pm 1^{\circ}\text{F}$ ($70^{\circ}\text{C} \pm 1^{\circ}\text{C}$) for a period of 24 hours.

4.16.3.2 The compression set of the sample of gasket material so tested shall not exceed 15 percent of the original thickness.

4.17 Marking. The fire hose connection or fitting shall be permanently and legibly marked on the outside surface of the product, with the manufacturer's name or trademark, the thread size, and designation (e.g., 1½ in. NH). Minimum letter height shall be 0.1 in. (2.55 mm). Also, the fire hose connection or fitting shall be permanently and legibly marked on the outside surface of the product, with the country of manufacturing origin.

Chapter 5 Screw Threads for Couplings and Adapters

5.1 Basic Form of Thread.

5.1.1 Basic thread form, as specified in Figure 5.1.1, shall have an included angle of 60 degrees and truncated top and bottom.

5.1.2 The basic angle of the thread between the sides of the thread measured in an axial plane shall be 60 degrees. The line bisecting this 60-degree angle shall be perpendicular to the axis of the screw thread.

5.1.3 The flat at the root and crest of the basic thread, as specified in Figure 5.1.1, shall be $\frac{1}{8}$ times the pitch or 0.125 times the pitch (p).

5.1.4 The height of the basic thread shall be

$$h = 0.649519 \times p$$

or

$$h = \frac{0.649519}{n}$$

[5.1.4]

where:

h = basic thread height in inches

p = pitch in inches ($p = 1/n$)

n = number of threads per inch

5.1.5* Blunt Start.

5.1.5.1 The outer ends of all external and internal threads shall be terminated by the blunt start, or Higbee cut, as shown in Figure 5.1.5.1, on full thread to avoid crossing and mutilation of thread.

5.1.5.2 The blunt start shall have a minimum length of not less than the radius formed by a cutter with a radius not less than the height of the thread.

5.1.5.3 The maximum length of the blunt start shall not exceed 10 degrees of arc.

5.2 Thread Series Designation.

5.2.1* Fire hose connection threads that meet the requirements of this chapter shall be identified as “American National Fire Hose Connection Screw Threads” (abbreviated throughout the standard with the thread symbol NH).





FIGURE 5.1.1 Form of Thread of American National Fire Hose Connection Screw Thread (NH) (See Table 5.4.1 for dimensions.)



C = Inside diameter of connection waterway (nominal size of connection)
 D = Approximate outside diameter of external thread (ODM)
 H = Depth of internal connection
 I = Length of the pilot from the face of the external connection to the start of the second thread (Higbee cut)
 J = Distance from the face of the internal connection to the start of the second thread (Higbee cut)
 K = Diameter of the gasket seat
 L = Length of external thread
 T = Length of internal thread

FIGURE 5.1.5.1 Nominal Dimensions of Connections (See Table 5.4.2 for dimensions.)

5.2.2 The fire hose connection threads shall be designated by specifying in sequence the nominal size of the connection, the number of threads per inch, and the thread symbol "NH" as shown in the following example:

0.75-8 NH	3.5-6 NH
1-8 NH	4-4 NH
1.5-9 NH	4.5-4 NH
2.5-7.5 NH	5-4 NH
3-6 NH	6-4 NH
	8-4 NH

5.3 Dimensions of American National Fire Hose Connection Screw Threads (NH).

5.3.1 The basic major diameter, basic pitch diameter, and basic minor diameter and tolerances of the thread shall be as specified in Figure 5.1.1.

5.3.2 Nominal dimensions shall be as specified in Figure 5.1.5.1.

5.4 Thread Dimensions.

5.4.1 The basic dimensions for the threads shall be as specified in Table 5.4.1.

5.4.2 The nominal dimensions for the threads shall be as specified in Table 5.4.2.

5.4.3 The limiting dimensions for external threads (nipples) shall be as specified in Table 5.4.3.

5.4.4 The limiting dimensions for internal threads (couplings) shall be as specified in Table 5.4.4.

5.5 Tolerance.

5.5.1 The pitch-diameter tolerances for a mating external (nipple) and internal (coupling) thread shall be the same.

5.5.1.1 Pitch-diameter tolerances shall include lead and half-angle deviations.

Table 5.4.1 Basic Dimensions of NH Threads (See Figure 5.1.1.)

Nominal Size of Connection	Threads per Inch (tpi)	Thread Designation (NH)	Pitch (p)	Basic Thread Height (h)	External Thread Dimensions (Nipple)				Minimum Internal Thread Dimensions		
					Allowance	Maximum Major Diameter, D - Col. 6	Maximum Pitch Diameter, Col. 7 - h	Maximum Minor Diameter, Col. 7 - 2h	Minimum Minor Diameter, D - 2h	Basic Pitch Diameter, D - h	Basic Major Diameter, D
1	2	3	4	5	6	7	8	9	10	11	12
¾	8	0.75-8 NH	0.12500	0.08119	0.0120	1.3750	1.2938	1.2126	1.2246	1.3058	1.3870
1	8	1-8 NH	0.12500	0.08119	0.0120	1.3750	1.2938	1.2126	1.2246	1.3058	1.3870
1½	9	1.5-9 NH	0.11111	0.07217	0.0120	1.9900	1.9178	1.8457	1.8577	1.9298	2.0020
2½	7.5	2.5-7.5 NH	0.13333	0.08660	0.0150	3.0686	2.9820	2.8954	2.9104	2.9970	3.0836
3	6	3-6 NH	0.16667	0.10825	0.0150	3.6239	3.5156	3.4073	3.4223	3.5306	3.6389
3½	6	3.5-6 NH	0.16667	0.10825	0.0200	4.2439	4.1356	4.0273	4.0473	4.1556	4.2639
4	4	4-4 NH	0.25000	0.16238	0.0250	5.0109	4.8485	4.6861	4.7111	4.8735	5.0359
4½	4	4.5-4 NH	0.25000	0.16238	0.0250	5.7609	5.5985	5.4361	5.4611	5.6235	5.7859
5	4	5-4 NH	0.25000	0.16238	0.0250	6.2600	6.0976	5.9352	5.9602	6.1226	6.2850
6	4	6-4 NH	0.25000	0.16238	0.0250	7.0250	6.8626	6.7002	6.7252	6.8876	7.0500
8	4	8-4 NH	0.25000	0.16238	0.0250	9.0250	8.8626	8.7002	8.7252	8.8876	9.0500

Note: All values are in inches except for columns 2 and 3.

Table 5.4.2 Nominal Dimensions of NH Threads (See Figure 5.1.5.1.)

Nominal Size of Connection Waterway, <i>C</i>	Threads per Inch (tpi)	Thread Designation (NH)	Approximate Outside Diameter of External Thread, <i>D</i> *	Length of External Thread (Min), <i>L</i>	Length of Pilot to Start of Second Thread (External), <i>I</i>	Depth of Internal Connector, <i>H</i>	Diameter of Gasket Seat in Coupling, <i>K</i>	Length of Internal Thread, <i>T</i>	Length of Pilot to Start of Second Thread (Internal), <i>J</i>
1	2	3	4	5	6	7	8	9	10
3/4	8	0.75-8 NH	1 3/8	5/8	5/32	19/32	1 1/16	13/32	5/32
1	8	1-8 NH	1 3/8	5/8	5/32	19/32	1 1/16	13/32	5/32
1 1/2	9	1.5-9 NH	2	5/8	5/32	19/32	2 1/16	13/32	5/32
2 1/2	7 1/2	2.5-7.5 NH	3 1/16	1	1/4	15/16	3 3/16	11/16	3/16
3	6	3-6 NH	3 3/8	1 1/8	5/16	1 1/16	3 3/4	3/4	1/4
3 1/2	6	3.5-6 NH	4 1/4	1 1/8	5/16	1 1/16	4 3/8	3/4	1/4
4	4	4-4 NH	5	1 1/4	7/16	1 3/16	5 1/8	7/8	3/8
4 1/2	4	4.5-4 NH	5 3/4	1 1/4	7/16	1 3/16	5 7/8	7/8	3/8
5	4	5-4 NH	6 1/4	1 3/8	7/16	1 5/16	6 3/8	1	3/8
6	4	6-4 NH	7 1/32	1 3/8	7/16	1 5/16	7 1/8	1	3/8
8	4	8-4 NH	9 1/32	1 1/2	7/16	1 7/16	9 1/8	1 1/8	3/8

Note: All values are in inches except for columns 2 and 3.

*Approximate dimensions are for field identification purposes only. Exact basic manufacturing dimensions and tolerances are given in subsequent tables.

Table 5.4.3 Limits of Size and Tolerances of NH External Threads (Nipples)

Nominal Size of Connection	Threads per Inch (tpi)	Thread Designation (NH)	Pitch (<i>p</i>)	Basic Thread Height (<i>h</i>)	External Thread (Nipple)						
					Major Diameter			Pitch Diameter			Minor Diameter*
					Maximum	Minimum	Tolerance	Maximum	Minimum	Tolerance	Maximum
1	2	3	4	5	6	7	8	9	10	11	12
3/4	8	0.75-8 NH	0.12500	0.08119	1.3750	1.3528	0.0222	1.2938	1.2827	0.0111	1.2126
1	8	1-8 NH	0.12500	0.08119	1.3750	1.3528	0.0222	1.2938	1.2827	0.0111	1.2126
1 1/2	9	1.5-9 NH	0.11111	0.07217	1.9900	1.9678	0.0222	1.9178	1.9067	0.0111	1.8457
2 1/2	7.5	2.5-7.5 NH	0.13333	0.08660	3.0686	3.0366	0.0320	2.9820	2.9660	0.0160	2.8954
3	6	3-6 NH	0.16667	0.10825	3.6239	3.5879	0.0360	3.5156	3.4976	0.0180	3.4073
3 1/2	6	3.5-6 NH	0.16667	0.10825	4.2439	4.2079	0.0360	4.1356	4.1176	0.0180	4.0273
4	4	4-4 NH	0.25000	0.16238	5.0109	4.9609	0.0500	4.8485	4.8235	0.0250	4.6861
4 1/2	4	4.5-4 NH	0.25000	0.16238	5.7609	5.7109	0.0500	5.5985	5.5735	0.0250	5.4361
5	4	5-4 NH	0.25000	0.16238	6.2600	6.2100	0.0500	6.0976	6.0726	0.0250	5.9352
6	4	6-4 NH	0.25000	0.16238	7.0250	6.9750	0.0500	6.8626	6.8376	0.0250	6.7002
8	4	8-4 NH	0.25000	0.16238	9.0250	8.9750	0.0500	8.8626	8.8376	0.0250	8.7002

Note: All values are in inches except for columns 2 and 3.

*Dimensions given for the maximum minor diameter of the nipple are figured to the intersection of the worn tool arc with a centerline through crest and root. The minimum minor diameter of the nipple shall be that corresponding to a flat at the minor diameter of the minimum nipple equal to $p/24$ and may be determined by subtracting $11 h/9$ (or $0.7939p$) from the minimum pitch diameter of the nipple.

Table 5.4.4 Thread Limits of Size and Tolerances of NH Internal Threads (Couplings)

Nominal Size of Connection	Threads per Inch (tpi)	Thread Designation (NH)	Pitch (p)	Basic Thread Height (h)	Internal Thread (Coupling)						
					Minor Diameter			Pitch Diameter			Major Diameter*
					Minimum	Maximum	Tolerance	Minimum	Maximum	Tolerance	
1	2	3	4	5	6	7	8	9	10	11	12
3/4	8	0.75-8 NH	0.12500	0.08119	1.2246	1.2468	0.0222	1.3058	1.3169	0.0111	1.3870
1	8	1-8 NH	0.12500	0.08119	1.2246	1.2468	0.0222	1.3058	1.3169	0.0111	1.3870
1 1/2	9	1.5-9 NH	0.11111	0.07217	1.8577	1.8799	0.0222	1.9298	1.9409	0.0111	2.0020
2 1/2	7.5	2.5-7.5 NH	0.13333	0.08660	2.9104	2.9424	0.0320	2.9970	3.0130	0.0160	3.0836
3	6	3-6 NH	0.16667	0.10825	3.4223	3.4583	0.0360	3.5306	3.5486	0.0180	3.6389
3 1/2	6	3.5-6 NH	0.16667	0.10825	4.0473	4.0833	0.0360	4.1556	4.1736	0.0180	4.2639
4	4	4-4 NH	0.25000	0.16238	4.7111	4.7611	0.0500	4.8735	4.8985	0.0250	5.0359
4 1/2	4	4.5-4 NH	0.25000	0.16238	5.4611	5.5111	0.0500	5.6235	5.6485	0.0250	5.7859
5	4	5-4 NH	0.25000	0.16238	5.9602	6.0102	0.0500	6.1226	6.1476	0.0250	6.2850
6	4	6-4 NH	0.25000	0.16238	6.7252	6.7752	0.0500	6.8876	6.9126	0.0250	7.0500
8	4	8-4 NH	0.25000	0.16238	8.7252	8.7752	0.0500	8.8876	8.9126	0.0250	9.0500

Note: All values are in inches except for columns 2 and 3.

*Dimensions for the minimum major diameter of the coupling correspond to the basic flat $p/8$, and the profile at the major diameter produced by a worn tool must not fall below the basic outline. The maximum major diameter of the coupling shall be that corresponding to a flat at the major diameter of the maximum coupling equal to $p/24$ and can be determined by adding $11h/9$ (or $0.7939p$) to the maximum pitch diameter of the coupling.

5.5.1.2 Values for lead and half-angle deviations consuming one-half of the pitch-diameter tolerance shall be as specified in Table 5.5.1.2.

5.5.2 The tolerance relationships for the external (nipple) threads shall be as follows:

$$\text{Major diameter tolerance} = 2 \times \text{pitch diameter tolerance}$$

$$\text{Minor diameter tolerance} = \text{pitch diameter tolerance} + 2h/9.$$

5.5.2.1 The minimum minor diameter of the external thread (nipple) shall be such as to result in a flat equal to $1/3$ of the $p/8$ basic flat ($p/24$) at the root when the pitch diameter of the nipple is at its minimum value.

5.5.2.2 The maximum minor diameter is basic but shall be permitted to be such as results from the use of a worn or rounded threading tool.

5.5.2.3 The maximum minor diameter shall be as specified in Figure 5.1.1 and is the diameter on which the minor diameter tolerance formula shown in 5.5.2 shall be based.

Table 5.5.1.2 Lead and Half-Angle Deviations Consuming One-Half of Pitch-Diameter Tolerances for NH Threads

Nominal Size of Connection	Thread per Inch (tpi)	Thread Designation (NH)	Pitch-Diameter Tolerance ^a	Lead Deviation Consuming One-Half of Pitch-Diameter Tolerance ^b	Half-Angle Deviation Consuming One-Half of Pitch-Diameter Tolerance	
					Degree	Minute
1	2	3	4	5	6	7
3/4	8	0.75-8 NH	0.0111	0.0032	1	42
1	8	1-8 NH	0.0111	0.0032	1	42
1 1/2	9	1.5-9 NH	0.0111	0.0032	1	54
2 1/2	7.5	2.5-7.5 NH	0.0160	0.0046	2	17
3	6	3-6 NH	0.0180	0.0052	2	4
3 1/2	6	3.5-6 NH	0.0180	0.0052	2	4
4	4	4-4 NH	0.0250	0.0072	1	55
4 1/2	4	4.5-4 NH	0.0250	0.0072	1	55
5	4	5-4 NH	0.0250	0.0072	1	55
6	4	6-4 NH	0.0250	0.0072	1	55
8	4	8-4 NH	0.0250	0.0072	1	55

Note: All values are in inches except for columns 2, 3, and 6.

^aThe tolerances specified for pitch diameter include all deviations of pitch diameter, lead, and angle. The full tolerance cannot, therefore, be used on pitch diameter unless the lead and angle of the thread are perfect. The last two columns give, for information, the deviations in lead and in angle, each of which can be compensated for by half the pitch-diameter tolerance given in this column. If lead and angle deviations both exist to the amount tabulated, the pitch diameter of a nipple, for example, must be reduced by the full tolerance or it will not enter the GO gauge.

^bBetween any two threads not farther apart than the length of engagement.

5.5.3 The tolerance relationships for the internal (coupling) threads shall be as follows:

$$\text{Minor diameter tolerance} = 2 \times \text{pitch diameter tolerance}$$

$$\text{Major diameter tolerance} = \text{pitch diameter tolerance} + 2h/g.$$

5.5.3.1 The minimum minor diameter of a coupling shall be such as to result in a basic flat, $p/8$, at the crest when the pitch diameter of the coupling is at its minimum value.

5.6 Gauges and Gauging NH Threads.

Δ 5.6.1 The limits of size for the gauges to be used in the gauging of fire hose connections shall be as specified in Table 5.6.1(a), Table 5.6.1(b), and Table 5.6.1(c).

5.6.2 For these gauges, the allowable variation in lead between any two threads not farther apart than the length of engagement shall be ± 0.0004 in. The allowable variation in half-angle of thread shall be ± 5 minutes.

5.6.3* Except as otherwise specified herein, the gauges and gauging practices shall conform to ANSI/ASME B1.2, *Gages and Gaging for Unified Inch Screw Threads*.

5.6.4* Adjustable thread ring gauges shall be set by means of threaded setting plug gauges, the dimensions of which are given in Table 5.6.1(a). Means of setting ring gauges shall be as specified in ANSI/ASME B1.2, *Gages and Gaging for Unified Inch Screw Threads*.

Δ Table 5.6.1(a) Setting Thread Plug Limits of Size for NH Thread Ring Gauges

Nominal Size of Connection	Threads per Inch (tpi)	Thread Designation (NH)		X Truncated Setting Plugs						X Basic-Crest Setting Plugs*	
				Plug for GO Thread Gauge			Plug for LO (NOT GO) Thread Gauge			Major Diameter	
				Major Diameter		Pitch Diameter	Major Diameter		Pitch Diameter	Plug for GO Thread Gauge	Plug for LO (NOT GO) Thread Gauge
				Truncated	Full		Truncated	Full			
Gauge Tolerance				-	+	-	-	+	+	+	+
1	2	3	4	5	6	7	8	9	10	11	12
¾	8	0.75-8 NH	Max Min	1.3579 1.3572	1.3757 1.3750	1.2938 1.2934	1.3368 1.3361	1.3757 1.3750	1.2831 1.2827	1.3757 1.3750	1.3757 1.3750
1	8	1-8 NH	Max Min	1.3579 1.3572	1.3757 1.3750	1.2938 1.2934	1.3368 1.3361	1.3757 1.3750	1.2831 1.2827	1.3757 1.3750	1.3757 1.3750
1½	9	1.5-9 NH	Max Min	1.9742 1.9735	1.9907 1.9900	1.9178 1.9174	1.9548 1.9541	1.9907 1.9900	1.9071 1.9067	1.9907 1.9900	1.9907 1.9900
2½	7.5	2.5-7.5 NH	Max Min	3.0507 3.0500	3.0693 3.0686	2.9820 2.9815	3.0237 3.0230	3.0693 3.0686	2.9665 2.9660	3.0693 3.0686	3.0693 3.0686
3	6	3-6 NH	Max Min	3.6029 3.6021	3.6247 3.6239	3.5156 3.5151	3.5698 3.5690	3.6247 3.6239	3.4981 3.4976	3.6247 3.6239	3.6247 3.6239
3½	6	3.5-6 NH	Max Min	4.2229 4.2216	4.2452 4.2439	4.1356 4.1350	4.1898 4.1885	4.2452 4.2439	4.1182 4.1176	4.2452 4.2439	4.2452 4.2439
4	4	4-4 NH	Max Min	4.9828 4.9813	5.0124 5.0109	4.8485 4.8479	4.9318 4.9303	5.0124 5.0109	4.8241 4.8235	5.0124 5.0109	5.0124 5.0109
4½	4	4.5-4 NH	Max Min	5.7328 5.7313	5.7624 5.7609	5.5985 5.5979	5.6818 5.6803	5.7624 5.7609	5.5741 5.5735	5.7624 5.7609	5.7624 5.7609
5	4	5-4 NH	Max Min	6.2319 6.2304	6.2615 6.2600	6.0976 6.0970	6.1809 6.1794	6.2615 6.2600	6.0732 6.0726	6.2615 6.2600	6.2615 6.2600
6	4	6-4 NH	Max Min	6.9969 6.9954	7.0265 7.0250	6.8626 6.8620	6.9459 6.9444	7.0265 7.0250	6.8382 6.8376	7.0265 7.0250	7.0265 7.0250
8	4	8-4 NH	Max Min	8.9969 8.9954	9.0265 9.0250	8.8626 8.8620	8.9459 8.9444	9.0265 9.0250	8.8382 8.8376	9.0265 9.0250	9.0265 9.0250

Notes:

(1) Gauge limit values in this table have been obtained in accordance with ANSI/ASME B1.2, *Gages and Gaging for Unified Inch Screw Threads*.

(2) All other values are in inches.

*Pitch-diameter limits for basic-crest GO setting plugs are the same as those shown in column 7. Pitch-diameter limits for basic-crest LO (NOT GO) setting plugs are the same as those shown in column 10.

Table 5.6.1(b) Gauge Limits of Size for Ring Gauges for NH External (Nipple) Threads

Nominal Size of Connection	Threads per Inch (tpi)	Thread Designation (NH)		X Thread Ring Gauges				Z Plain Ring Gauges	
				GO		LO (NOT GO)		Major Diameter	
				Pitch Diameter	Minor Diameter	Pitch Diameter	Minor Diameter	GO	NOT GO
Gauge Tolerance				-	-	+	+	-	-
1	2	3	4	5	6	7	8	9	10
¾	8	0.75-8 NH	Max Min	1.2938	1.2246	1.2831	1.2563	1.37500	1.35292
				1.2934	1.2239	1.2827	1.2556	1.37488	1.35280
1	8	1-8 NH	Max Min	1.2938	1.2246	1.2831	1.2563	1.37500	1.35292
				1.2934	1.2239	1.2827	1.2556	1.37488	1.35280
1½	9	1.5-9 NH	Max Min	1.9178	1.8577	1.9071	1.8833	1.99000	1.96796
				1.9174	1.8570	1.9067	1.8826	1.98984	1.96780
2½	7.5	2.5-7.5 NH	Max Min	2.9820	2.9104	2.9665	2.9378	3.06860	3.03680
				2.9815	2.9097	2.9660	2.9371	3.06840	3.03660
3	6	3-6 NH	Max Min	3.5156	3.4223	3.4981	3.4623	3.62390	3.58810
				3.5151	3.4215	3.4976	3.4615	3.62370	3.58790
3½	6	3.5-6 NH	Max Min	4.1356	4.0473	4.1182	4.0828	4.24390	4.20810
				4.1350	4.0460	4.1176	4.0815	4.24370	4.20790
4	4	4-4 NH	Max Min	4.8485	4.7111	4.8241	4.7709	5.01090	4.96115
				4.8479	4.7096	4.8235	4.7694	5.01065	4.96090
4½	4	4.5-4 NH	Max Min	5.5985	5.4611	5.5741	5.5209	5.76090	5.71115
				5.5979	5.4596	5.5735	5.5194	5.76065	5.71090
5	4	5-4 NH	Max Min	6.0976	5.9602	6.0732	6.0200	6.26000	6.21025
				6.0970	5.9587	6.0726	6.0185	6.25975	6.21000
6	4	6-4 NH	Max Min	6.8626	6.7252	6.8382	6.7850	7.02500	6.97532
				6.8620	6.7237	6.8376	6.7835	7.02468	6.97500
8	4	8-4 NH	Max Min	8.8626	8.7252	8.8382	8.7850	9.02500	8.97532
				8.8620	8.7237	8.8376	8.7835	9.02468	8.97500

Notes:

(1) Gauge limit values in this table have been obtained in accordance with ANSI/ASME B1.2, *Gages and Gaging for Unified Inch Screw Threads*, except for the values shown in column 6. The maximum values shown in column 6 are values for the minimum minor diameter of the internal thread.

(2) All other values are in inches.

Table 5.6.1(c) Gauge Limits of Size for Plug Gauges for NH Internal (Coupling) Threads

Nominal Size of Connection	Threads per Inch (tpi)	Thread Designation (NH)		X Thread Plug Gauges				Z Plain Plug Gauges	
				GO		HI (NOT GO)		Minor Diameter	
				Major Diameter	Pitch Diameter	Major Diameter	Pitch Diameter	GO	NOT GO
Gauge Tolerance				+	+	-	-	+	-
1	2	3	4	5	6	7	8	9	10
¾	8	0.75-8 NH	Max Min	1.3877 1.3870	1.3062 1.3058	1.3710 1.3703	1.3169 1.3165	1.22472 1.22460	1.24680 1.24668
1	8	1-8 NH	Max Min	1.3877 1.3870	1.3062 1.3058	1.3710 1.3703	1.3169 1.3165	1.22472 1.22460	1.24680 1.24668
1½	9	1.5-9 NH	Max Min	2.0027 2.0020	1.9302 1.9298	1.9890 1.9883	1.9409 1.9405	1.85786 1.85770	1.87990 1.87974
2½	7.5	2.5-7.5 NH	Max Min	3.0843 3.0836	2.9975 2.9970	3.0707 3.0700	3.0130 3.0125	2.91060 2.91040	2.94240 2.94220
3	6	3-6 NH	Max Min	3.6397 3.6389	3.5311 3.5306	3.6208 3.6200	3.5486 3.5481	3.42250 3.42230	3.45830 3.45810
3½	6	3.5-6 NH	Max Min	4.2652 4.2639	4.1562 4.1556	4.2458 4.2445	4.1736 4.1730	4.04750 4.04730	4.08330 4.08310
4	4	4-4 NH	Max Min	5.0374 5.0359	4.8741 4.8735	5.0068 5.0053	4.8985 4.8979	4.71135 4.71110	4.76110 4.76085
4½	4	4.5-4 NH	Max Min	5.7874 5.7859	5.6241 5.6235	5.7568 5.7553	5.6485 5.6479	5.46135 5.46110	5.51110 5.51085
5	4	5-4 NH	Max Min	6.2865 6.2850	6.1232 6.1226	6.2559 6.2544	6.1476 6.1470	5.96045 5.96020	6.01020 6.00995
6	4	6-4 NH	Max Min	7.0515 7.0500	6.8882 6.8876	7.0209 7.0194	6.9126 6.9120	6.72552 6.72520	6.77520 6.77488
8	4	8-4 NH	Max Min	9.0515 9.0500	8.8882 8.8876	9.0209 9.0194	8.9126 8.9120	8.72552 8.72520	8.77520 8.77488

Notes:

(1) Gauge limit values in this table have been obtained in accordance with ANSI/ASME B1.2, *Gages and Gaging for Unified Inch Screw Threads*.

(2) All other values are in inches.

Chapter 6 Nonthreaded Connections

6.1* General. The requirements of Chapters 1 through 4 and the requirements of this chapter shall apply to nonthreaded connections in the 4 in. (100 mm) and 5 in. (125 mm) sizes.

6.2* Gauges.

6.2.1 The dimensional characteristics and tolerances for the metal-face gauges to be used in the gauging of nonthreaded connections shall be as specified in Figure 6.2.1(a) for a Type A test gauge and Figure 6.2.1(b) for a Type B test gauge.

6.2.2 In addition, the 4 in. (100 mm) metal-face gauge shall meet the dimensional characteristics of Figure 6.2.2(a), and the 5 in. (125 mm) metal-face gauge shall meet the dimensional characteristics of Figure 6.2.2(b).

6.3 Locks.

6.3.1* All gasketed nonthreaded connections shall be provided with locks within the confines of the nonthreaded connection to ensure against unintentional disconnection.

6.3.2 Caps for use with nonthreaded connections shall be permitted without a lock.


6.3.3 The locks shall be located so that the nonthreaded connection will connect to the Type A metal-face test gauge and lock.

6.3.4 The locks shall be designed so as to lock automatically when connecting two nonthreaded connections without additional action needed to engage the locks. The lock shall not be capable of being secured (mechanically) in the open (unlocked) position.

6.3.5 The locks shall be field repairable.

6.3.6 The locks shall be designed so as to be disengaged by hand in a separate action other than that needed to disconnect the nonthreaded connection.

Δ 6.3.6.1 The locks shall be capable of being unlocked by a fire fighter wearing gloves meeting the requirements of NFPA 1971.




Notes:

(1) All linear measurements in inches. Tolerances: X.XXX ± 0.005 in. unless otherwise noted.

(2) All dimensions are to be the same for similar configurations on gauges.

Δ FIGURE 6.2.1(a) Dimensions for Type A Test Gauge (No Ramp Angle).



▲ FIGURE 6.2.1(b) Dimensions for Type B Test Gauge (with Lugs Removed).

6.3.6.2 A device such as a wrench incorporating actions to disengage the lock and disconnect the nonthreaded connection in one motion shall be permitted to be used.

6.3.7 The lock mechanism shall not shear when a force of 300 lb × ft (407 N × m) is applied at the nut on the test wrench.

6.4 Indicators. Permanent indicators, obvious to sight and touch, shall be located at two points 180 degrees apart, as shown on Figure 6.2.2(a) and Figure 6.2.2(b), to indicate the fully engaged position of the connections.

6.5 Force to Connect and Disconnect.


6.5.1* All nonthreaded pressure connections shall be capable of connection and disconnection to both the Type A and the Type B metal-face test gauges at a force of between 6.0 lb × in. (0.68 N × m) and 30 lb × in. (3.4 N × m) when measured as described in 6.5.3 and under the conditions described in 6.5.4. The force to connect and disconnect nonthreaded pressure connections to each other shall not exceed 40 lb × in. (4.5 N ×

m) when measured as described in 6.5.3 and under the conditions described in 6.5.4.

6.5.2 All nonthreaded suction connections shall be capable of connection and disconnection to both the Type A and the Type B metal-face test gauges at a force of between 168 lb × in. (19.0 N × m) and 312 lb × in. (35.3 N × m) when measured as described in 6.5.3 and under the conditions described in 6.5.4. The force to connect and disconnect nonthreaded suction connections to each other shall not exceed 360 lb × in. (40.7 N × m) when measured as described in 6.5.3 and under the conditions described in 6.5.4.


6.5.3* The force to connect and disconnect shall be tested as described in 6.5.3.1 through 6.5.3.4.2.

6.5.3.1 One of the metal-face test gauges, or one-half of a pressure or suction connector, depending on the force to be checked, shall be secured in a vise or similar device. The connector to be tested shall be free to turn without constraint or assistance.



Note: All dimensions are to be the same for similar configurations on the gauge.

FIGURE 6.2.2(a) End View of 4 in. (100 mm) Metal-Face Gauge and Nonthreaded 4 in. (100 mm) Connections.



Note: All dimensions are to be the same for similar configurations on the gauge.

FIGURE 6.2.2(b) End View of 5 in. (125 mm) Metal-Face Gauge and Nonthreaded 5 in. (125 mm) Connections.

6.5.3.2 For 4 in. (100 mm) connectors, a test wrench with dimensions as shown in Figure 6.5.3.2(a) shall be attached over the external lugs of the connector being tested. For 5 in. (125 mm) connectors, a test wrench with dimensions as shown in Figure 6.5.3.2(b) shall be attached over the external lugs of the connector to be tested.

6.5.3.3 A standard torque wrench measuring inch-pounds shall be connected to the test wrench.

6.5.3.4 The torque wrench shall be moved in the direction necessary to connect or disconnect the connector being tested.

6.5.3.4.1 The lock shall be held open only when the connector is being disconnected.

6.5.3.4.2 The torque wrench shall be in direct line with the center of the connector when the torque reading is being taken.

6.5.4 The force to connect and disconnect test shall be done at 70°F (21°C) ambient temperature. The gaskets shall be clean but not lubricated.

6.6* Caps. All nonthreaded caps shall have gaskets installed.

6.6.1 Installation and Removal of Nonthreaded Caps.

6.6.1.1 Utilization without a tool. Nonthreaded caps designed to be removed without the use of a tool shall require a force between 6 lbf in. and 30 lbf in. to install and remove.

6.6.1.2 Utilization with a tool. Nonthreaded caps designed for the use of a tool to remove shall require a force of 168 lbf in. to 312 lbf in. to install and remove.

6.6.2* The cap used for a nonthreaded fire department connection shall be provided with a means of indicating water pressure behind the cap.


6.7 Adapters. All nonthreaded adapters shall have gaskets installed.

6.8 Hydrant and Fire Department Connections.

6.8.1 Nonthreaded hydrant and fire department connections shall be metal-faced, without gaskets.

6.8.2 Nonthreaded hydrant and fire department connections shall be made to the dimensions specified in Figure 6.8.2.

6.8.3 In addition, 4 in. (100 mm) metal-faced hydrant and fire department connections shall meet the dimensional characteristics of Figure 6.2.2(a), and the 5 in. (125 mm) metal-faced hydrant and fire department connections shall meet the dimensional characteristics of Figure 6.2.2(b).



Size	A	B	C	D	E	F	G	H	I	J	K	L	M	N	P	Q
4 in.	5.500	5.472	5.197	5.118	4.528	3.500	0.190	0.576	0.236	0.532	4.500	0.213±.002	15°	35°	6.142	0.023±.002
5 in.	6.957	6.929	6.575	6.496	5.826	4.500	0.220	0.653	0.295	0.622	5.750	0.258±.002	16°	36°	7.717	0.038±.002

Notes:

- (1) All linear measurements in inches. Tolerances: X.XXX ± 0.005 in. unless otherwise noted; angles ±½ degree.
- (2) Attachment to hydrant or piping to fire department connection — as specified by purchaser.
- (3) All dimensions are to be the same for similar configurations on the hydrant or fire department connection.

FIGURE 6.8.2 Metal-Faced Hydrant and Fire Department Connections Showing Required Dimensions.

Chapter 7 Gaskets

7.1 Threaded Coupling Gasket.

7.1.1 Each internal connection shall be provided with a resilient thread gasket that does not leak under normal use when fitted accurately in the seat specified in this standard.

7.1.2 Each thread gasket shall meet the dimensions specified in Table 7.1.2.

7.1.3 The durometer of the thread gasket shall be 70 ± 5 Shore A.

7.2 Nonthreaded Connection Gaskets.

7.2.1 Each nonthreaded connection, with the exception of metal-faced hydrants and fire department connections that meet the requirement in Section 6.8, shall be fitted with a resilient face gasket that does not leak under normal use.

7.2.2 The durometer of the gasket shall be 70 ± 5 Shore A.

7.2.3 The face gasket shall be either a suction gasket or a pressure gasket, depending on the application in which the connection is to be used.

7.2.3.1 Pressure gaskets shall be designed to withstand the pressure requirements of Sections 4.6 and 4.10 without leakage. They shall be black in color.

7.2.3.2 Suction gaskets shall be designed to allow couplings equipped with the gasket to meet the requirements of Section 4.11. They shall be gray in color.

7.3* Tail Gasket.

7.3.1 Each coupling that is installed on a fire hose with an expansion ring shall be equipped with a resilient gasket of durometer 60 ± 5 Shore A in the hose bowl that keeps the ends of the fabric of the fire hose dry.

7.3.2 The nominal dimensions of these gaskets shall be as follows:

- (1) Minimum inside diameter as specified in Table 7.1.2
- (2) Outside diameter to accurately fit the recess provided
- (3) Thickness $\frac{3}{16}$ in. (4.8 mm) minimum

Table 7.1.2 Dimensions of Thread Gaskets for Standard Internal Threaded Connections

Nominal Size of Connection (in.)	Inside Diameter		Outside Diameter		Thickness	
	in.	mm	in.	mm	in.	mm
$\frac{3}{4}$	$\frac{13}{16}$	20.6	$1\frac{7}{16}$	36.5	$\frac{1}{8}$	3.18
1	$1\frac{1}{16}$	27	$1\frac{7}{16}$	36.5	$\frac{1}{8}$	3.18
$1\frac{1}{2}$	$1\frac{9}{16}$	40	$2\frac{1}{16}$	52	$\frac{1}{8}$	3.18
$2\frac{1}{2}$	$2\frac{9}{16}$	65	$3\frac{3}{16}$	81	$\frac{3}{16}$	4.8
3	$3\frac{1}{16}$	78	$3\frac{3}{4}$	95	$\frac{1}{4}$	6.4
$3\frac{1}{2}$	$3\frac{7}{16}$	91	$4\frac{3}{8}$	111	$\frac{1}{4}$	6.4
4	$4\frac{1}{16}$	103	$5\frac{1}{8}$	130	$\frac{1}{4}$	6.4
$4\frac{1}{2}$	$4\frac{9}{16}$	117	$5\frac{7}{8}$	149	$\frac{1}{4}$	6.4
5	$5\frac{1}{16}$	129	$6\frac{3}{8}$	162	$\frac{1}{4}$	6.4
6	$6\frac{1}{16}$	154	$7\frac{1}{8}$	181	$\frac{1}{4}$	6.4
8	$8\frac{1}{16}$	205	$9\frac{1}{8}$	232	$\frac{1}{4}$	6.4

Chapter 8 Use of NH Threads and Nonthreaded Connections**8.1* Hose Coupling Threads.**

8.1.1* $\frac{3}{4}$ in. and 1 in. (19 mm and 25 mm) Hose. All $\frac{3}{4}$ in. and 1 in. (19 mm and 25 mm) hose shall be provided with couplings having the 0.75-8 NH standard thread and 1-8 NH standard thread, respectively.

8.1.2 $1\frac{1}{2}$ in. Through 2 in. (38 mm Through 52 mm) Fire Hose. All $1\frac{1}{2}$ in. through 2 in. (38 mm through 52 mm) fire hose shall be provided with couplings having the 1.5-9 NH standard thread.

8.1.3 $2\frac{1}{2}$ in. (65 mm) Fire Hose. All $2\frac{1}{2}$ in. (65 mm) fire hose shall be provided with couplings having the 2.5-7.5 NH standard thread.

8.1.4 3 in. (75 mm) Fire Hose. All 3 in. (75 mm) fire hose shall be provided with couplings having the 2.5-7.5 NH standard thread.

8.1.4.1 Where interchangeability with $2\frac{1}{2}$ in. (65 mm) fire hose is not required, the couplings shall be permitted to have the 3-6 NH standard thread.

8.1.5 $3\frac{1}{2}$ in. (90 mm) Fire Hose. All $3\frac{1}{2}$ in. (90 mm) fire hose shall be provided with couplings having the 3.5-6 NH standard thread.

8.1.5.1 Where interchangeability with 3 in. (75 mm) fire hose or other connections is required, the couplings shall be permitted to have the 3-6 NH standard thread.

8.1.6 4 in. (100 mm) Fire Hose. All 4 in. (100 mm) fire hose shall be provided with couplings having the 4-4 NH standard thread.

8.1.6.1 Where interchangeability with $3\frac{1}{2}$ in. (90 mm) fire hose or other connections is required, the couplings shall be permitted to have the 3.5-6 NH standard thread.

8.1.6.2 Where the authority having jurisdiction permits, 4 in. (100 mm) nonthreaded couplings shall be permitted to be used.

8.1.7 $4\frac{1}{2}$ in. (114 mm) Fire Hose. All $4\frac{1}{2}$ in. (114 mm) fire hose shall be provided with couplings having the 4.5-4 NH standard thread.

8.1.7.1 Where interchangeability with 4 in. (100 mm) fire hose or other connections is required, the couplings shall be permitted to have the 4-4 NH standard thread.

8.1.8 5 in. (125 mm) Fire Hose. All 5 in. (125 mm) fire hose shall be provided with couplings having the 5-4 NH standard thread.

8.1.8.1 Where interchangeability with $4\frac{1}{2}$ in. (114 mm) fire hose or other connections is required, the couplings shall be permitted to have the 4.5-4 NH standard thread.

8.1.8.2 Where the authority having jurisdiction permits, 5 in. (125 mm) nonthreaded couplings shall be permitted to be used.

8.1.9 6 in. (150 mm) Fire Hose. All 6 in. (150 mm) fire hose shall be provided with couplings having the 6-4 NH standard thread.

8.1.9.1 Where interchangeability with 5 in. (125 mm) fire hose or other connections is required, the couplings shall be permitted to have the 5-4 NH standard thread.

8.1.10 8 in. (200 mm) Fire Hose. All 8 in. (200 mm) fire hose shall be provided with couplings having the 8-4 NH standard thread.

8.1.11 Suction Hose. Suction hose shall be provided with couplings having the NH standard thread compatible with the nominal size of the suction hose.

8.2* Connections for Fire Service Nozzles for Handlines.

8.2.1 Playpipes for connecting shutoff nozzles to $2\frac{1}{2}$ in. (65 mm) fire hose shall have the 2.5-7.5 NH standard thread at the base or primary inlet and the 1.5-9 NH standard thread at the discharge end, as shown in Figure 8.2.1.

8.2.2 Nozzle shutoff valves for either $2\frac{1}{2}$ in. (65 mm) nozzles or $1\frac{1}{2}$ in. (38 mm) nozzles shall have the 1.5-9 NH standard thread for both the inlet and discharge sides of the valve, as shown in Figure 8.2.1 for $2\frac{1}{2}$ in. (65 mm) and Figure 8.2.2 for $1\frac{1}{2}$ in. (38 mm).

8.2.2.1 Where the valve is an integral nondetachable part of a $2\frac{1}{2}$ in. (65 mm) playpipe, the 1.5-9 NH standard thread shall be provided only on the discharge side of the valve.




FIGURE 8.2.1 Nozzle Assembly for 2½ in. (65 mm) Hose.




FIGURE 8.2.2 Nozzle Assembly for 1½ in. (38 mm) Hose.

8.2.3 All nozzles used on booster hose shall have the 1-8 NH standard thread.

8.2.4 All nozzle tips for use on 2½ in. (65 mm) and 1½ in. (38 mm) nozzles shall have the 1.5-9 NH standard thread.

8.2.5* All spray nozzles with a shutoff valve for use on 1½ in. (38 mm) and 2½ in. (65 mm) hose where flows at rated pressure do not exceed 400 gpm (1600 L/min) shall have at least the 1.5-9 NH standard thread at the internal connection.

8.3 Connections for Large-Stream Devices.

8.3.1* Primary Inlet. At least one inlet connection on each fire department large-stream device equipped with multiple primary inlets (other than devices piped permanently to a pump) shall be fitted with at least one female swivel connection, which shall have the 2.5-7.5 NH standard thread as shown in Figure 8.3.1(a) and Figure 8.3.1(b). An adapter shall be permitted to be provided to meet this intent.




FIGURE 8.3.1(a) Large-Stream Device Rated Under 1250 gpm (5000 L/min).




FIGURE 8.3.1(b) Large-Stream Device Rated Over 1250 gpm (5000 L/min) But Less Than 3000 gpm (12,000 L/min).

8.3.2* Subsequent Connections and Nozzles.

8.3.2.1 The discharge end of large-stream devices designed to discharge from 400 gpm to 1250 gpm (1600 L/min to 5000 L/min) shall have the 2.5-7.5 NH thread for attaching straight tip nozzle tips or spray nozzles.

8.3.2.1.1 If stacked straight tip nozzles are used, one of the tips shall have the 1.5-9 NH thread as shown in Figure 8.3.1(a).

8.3.2.1.2 Straight tip nozzles and spray nozzles designed to discharge between 400 gpm and 1250 gpm (1600 L/min and 5000 L/min) shall have the 2.5-7.5 NH thread on their inlet.

8.3.2.2 The discharge end of large-stream devices designed to discharge in excess of 1250 gpm (5000 L/min) but less than 3000 gpm (12,000 L/min) shall have the 3.5-6 NH thread for attaching straight tip nozzles or spray nozzles.

8.3.2.2.1 A 3.5-6 NH female \times 2.5-7.5 NH male reducer fitting, or a stacked tip having the male 2.5-7.5 NH thread as an integral component as shown in Figure 8.3.1(b) shall be provided.

8.3.2.2.2 Straight tip nozzles and spray nozzles designed to discharge flows in excess of 1250 gpm (5000 L/min) but less than 3000 gpm (12,000 L/min) shall have the 3.5-6 NH thread on their inlet.

8.3.2.3 Subsequent connections, straight tip nozzles, and spray nozzles on large-stream devices designed to discharge 3000 gpm (12,000 L/min) or more shall have an NH standard thread consistent with the nominal inlet or outlet size.

Annex A Explanatory Material

Annex A is not a part of the requirements of this NFPA document but is included for informational purposes only. This annex contains explanatory material, numbered to correspond with the applicable text paragraphs.

A.1.1 Some fire-fighting organizations use small hose less than $\frac{3}{4}$ in. (19 mm) nominal diameter fitted with garden hose couplings. Such couplings should have 0.75-11.5 NH (garden hose thread) threads conforming to ANSI/ASME B1.20.7, *Standard on Hose Coupling Screw Threads*.

A.3.2.1 Approved. The National Fire Protection Association does not approve, inspect, or certify any installations, procedures, equipment, or materials; nor does it approve or evaluate testing laboratories. In determining the acceptability of installations, procedures, equipment, or materials, the authority having jurisdiction may base acceptance on compliance with NFPA or other appropriate standards. In the absence of such standards, said authority may require evidence of proper installation, procedure, or use. The authority having jurisdiction

may also refer to the listings or labeling practices of an organization that is concerned with product evaluations and is thus in a position to determine compliance with appropriate standards for the current production of listed items.

A.3.2.2 Authority Having Jurisdiction (AHJ). The phrase “authority having jurisdiction,” or its acronym AHJ, is used in NFPA documents in a broad manner, since jurisdictions and approval agencies vary, as do their responsibilities. Where public safety is primary, the authority having jurisdiction may be a federal, state, local, or other regional department or individual such as a fire chief; fire marshal; chief of a fire prevention bureau, labor department, or health department; building official; electrical inspector; or others having statutory authority. For insurance purposes, an insurance inspection department, rating bureau, or other insurance company representative may be the authority having jurisdiction. In many circumstances, the property owner or his or her designated agent assumes the role of the authority having jurisdiction; at government installations, the commanding officer or departmental official may be the authority having jurisdiction.

A.4.1 Figure A.4.1(a) shows an expansion ring coupling set for a set of threaded couplings. Figure A.4.1(b) shows a typical nonthreaded fire hose connection that connects to the fire hose with a tailpiece and external reattachable collar.

A.5.1.5 Blunt starts are required on the entering ends of the NH screw thread on all sizes of fire hose connections that meet the requirements of this standard. The blunt start is formed by cutting off the entering ends of the screw threads completely to where, at the blunt start, the dimension from the face of the connection to the root of the start of the second thread is as specified in Table 5.4.2 (Column *I* for external threads and Column *J* for internal threads), as illustrated in Figure 5.1.5.1.




FIGURE A.4.1(a) An Expansion Ring Coupling Set.




FIGURE A.4.1(b) A Nonthreaded Fire Hose Connection.

When the entering threads are cut back as required, it forms a pilot on the male coupling and a counter bore in the female coupling, making it easier to align the connections and start the thread engagement.

When the starting ends of the threads are cut off, the following occur:

- (1) It takes fewer turns to connect the connection — over one turn less on a 2½ in. (65 mm) connection.
- (2) There are no threads at the ends of the connections to be damaged when dropped.
- (3) The sharp entering threads are gone, reducing cuts to hands.

A good blunt start does the following:

- (1) Helps ream dirt out of the threads when a coupling has been dropped in the dirt
- (2) Prevents cross-threading
- (3) Makes it easier and faster to connect fire hose connections

A.5.2.1 American National Fire Hose Connection Screw Threads are also sometimes known by the abbreviations NST and NS.

A.5.6.3 See Figure A.5.6.3.

A.5.6.4 Note that setting plug gauges is necessary only for setting of adjustable thread ring gauges and for checking solid ring gauges.

A.6.1 Figure A.6.1 shows the names of the various parts of a nonthreaded coupling.

A.6.2 The Type A test gauge checks the distance from under the high point of the two ramps of a nonthreaded connection to the corresponding connection's gasket face, which is at the centerline between the gauge and the connection when they are connected. The Type B test gauge checks the distance from under the two lugs of a nonthreaded connection to the corresponding connection's gasket face, which is at the centerline between the gauge and the connection when they are connected.

A.6.3.1 During the transition in a fire department from couplings without locks to couplings with locks, there will be times when hose will be coupled together with one coupling being a locking type and the other a nonlocking type. Because disconnection procedures are different for couplings with locks, consideration should be given to painting a ring in a distinctive color on the hose near the couplings with locks to alert the fire fighter to the presence of the lock.

A.6.5.1 The forces defined in this requirement are intended to provide nonthreaded connections that are able to be connected and disconnected easily by hand and without the use of wrenches when the connectors are not under pressure.

A.6.5.3 Figure A.6.5.3 shows an example of the setup and location of the torque wrench, test wrench, nonthreaded connector, and test gauge.

Other methods of measuring force to connect and disconnect can be used if they produce the same results. A second method of testing the force to connect and disconnect against the test gauges is to fit the metal-face gauge with a plug that has a hex head connection for the torque wrench on the back side of the gauge at the center of rotation. The nonthreaded connector to be tested is then held stationary in a vise or similar device, and the metal-face gauge is mated to the nonthreaded connection with the torque wrench measuring the amount of force to connect and disconnect the two parts. When the force is measured at any point other than as defined in 6.5.3, the acceptable range of force values will need to be calculated for the position of the torque wrench.


A.6.6 Suction gaskets will work in both pressure and suction applications but are difficult to compress by hand when mated to a pressure connection. In some areas a more tamper-resistant nonthread cap could be desired by the end user. Caps with a force between 6 lbf in. and 30 lbf in. to remove are considered readily removable by hand. Caps with a force between 168 lbf in. and 312 lbf in. to remove generally would require the use of a tool to remove.

A.6.6.2 A ⅛ in. (3.18 mm opn) diameter or larger hole in the cap that could be exposed to internal pressure can be used to indicate water is present.

A.7.3 It is important when ordering couplings and tail gaskets for recoupling hose with expansion ring couplings that the appropriate tail gasket be obtained. The coupling manufacturer needs the outside diameter of the hose and the wall thickness of the hose to provide the proper coupling and gasket. Also, the length of the expansion ring must be consistent with the length of the coupling bowl.

A.8.1 Where local fire hose coupling threads are not standard, swivel adapters, with the NH female thread and the local male thread, and with the local female thread and the NH male thread, should be carried on the apparatus, stored in hose houses, and so forth.

A.8.1.1 Some fire-fighting organizations use small hose less than ¾ in. (19 mm) nominal diameter fitted with garden hose couplings. Such couplings should have 0.75-11.5 NH (garden hose thread) threads conforming to ANSI/ASME B1.20.7, *Standard on Hose Coupling Screw Threads*.



[See Tables 5.6.1(b) and 5.6.1(c) for complete dimensions for these gauges.]

Note 1: The GO plain ring gauge and the GO plain plug gauge have not been included in this figure since the sharpness of the crests of the external and internal threads will be considered generally acceptable if the GO thread ring gauge and the GO thread plug gauge assemble on the two mating parts of the coupling.

Note 2: Internal threads are acceptable when the HI thread plug is applied to the coupling thread if (a) it does not enter, or if (b) all complete coupling threads can be entered, provided that a definite drag (from contact with the coupling material) results on or before the second turn of entry. The gauge should not be forced after the drag becomes definite.

Note 3: External threads are acceptable when the LO thread ring gauge is applied to the nipple thread if (a) it is not entered, or if (b) all complete nipple threads can be entered, provided that a definite drag (from contact with the nipple material) results from contact on or before the second turn of entry. The gauge should not be forced after the drag is definite.

FIGURE A.5.6.3 Gauges for 2.5-7.5 NH Threads.


A.8.2 Connections with NH threads covered in 8.2.1 through 8.2.5 should have adapters with the internal local thread preconnected to the appliance.

The various subsequent connections on a fire service nozzle are designed with standard NH thread to allow the nozzle tip to be removed and hose connected to extend the line. This operation is particularly beneficial when the attack starts with large hand-held lines, and these are later reduced to smaller lines for overhaul.

A.8.2.5 The use of the specified size thread makes it possible to attach these nozzles to any standard 2½ in. (65 mm) or 1½ in. (38 mm) playpipe or shutoff valve and also to advance the nozzle by connecting 1½ in. (38 mm) hose between the valve and the spray nozzle.

A.8.3.1 Fire department large-stream devices with a single large-diameter input are designed to rely on the positioning of the hose for part of the device's stability. The manufacturer's instructions for use should be carefully followed with all large-stream devices. A device designed with a single hose-line inlet system is different from a device designed with a multiline inlet system, and trying to supply one device with adapters and fittings from different size hose can create a dangerous situation.

A.8.3.2 A flow of 400 gpm (1600 L/min) is the maximum normally obtained with a handline nozzle using a standard 1¼ in. (32 mm) straight tip nozzle. A flow of 1250 gpm (5000 L/min) is the maximum normally obtained with a portable turret nozzle using a 2 in. (51 mm) straight tip nozzle.



Legend:

1. Circumferential O.D.: The largest outer diameter of connection that protects the connection from damage.
2. Coupling face: The front part of the connection from which dimensions are developed.
3. Internal lug: The two internal lugs with recesses that fit on the ramp under the face of the cam head.
4. Ramp: The inclined plane under the face of the cam head that, when turned clockwise, increases pressure on lip seals.
5. Lug stop: The stop at the end of the ramp that the internal lug comes against.
6. Lug recess: Recessed area where opposite internal lugs enter the ramp.
7. Cleaning port: Area on end of connection face where dirt is pushed in by mating lug.
8. External wrenching lug: The external ribs or lugs on back diameter of connection head.
9. External wrenching lug indicator: The identification on rib or lug that, when lined up together, indicates the connection is fully engaged.
10. Tail place recess: The recess counterbore on the interface of the cam head that the tail piece rides in.
11. Lock: To keep the connection from becoming unintentionally disengaged.

FIGURE A.6.1 Diagram of a Nonthreaded Connection.




FIGURE A.6.5.3 Arrangement for Testing Nonthreaded Connections.